


Fujitsu Mainboard

D3348-B2

BIOS Release Document



BIOS D3348-B2



Content:

1	General Notes	3
1.1	Released OS Versions	3
1.2	BIOS Update Options	3
1.3	Modify BIOS Setup Settings (Tool EditCMOS)	4
1.4	How to create a DOS bootable USB stick?	4
1.5	FTP BIOS Folder D3348-B	4
1.6	Note: Customer Service Release BIOS	4
2	BIOS R1.3.0	5
3	BIOS R1.5.0	6
4	BIOS R1.6.0	7
5	BIOS R1.10.0	8
6	BIOS R1.11.0	9
7	BIOS R1.14.0 [new]	10

Revision History:

Date	BIOS Version	Notes
16.04.2018	R1.14.0	New BIOS version (R1.14.0) added
23.08.2017	R1.11.0	New BIOS version (R1.11.0) added
13.06.2017	R1.10.0	New BIOS version (R1.10.0) added
18.08.2016	R1.6.0	New BIOS version (R1.6.0) added
20.07.2016	R1.5.0	New BIOS version (R1.5.0) added
25.05.2016	R1.3.0	Initial mass production release

1 General Notes

AMI Aptio V5.0.1.1 R1.x.x

1.1 Released OS Versions

- MS Windows 7 (64bit)
- MS Windows 8.1 (64bit)
- MS Windows Server 2012-R2 (64bit)

1.2 BIOS Update Options

DOS Flash Update

Use ZIP-files for DOS-based BIOS Update

→ Copy related files (folder "DOS") to a DOS-bootable device and run <DosFlash.BAT>

Windows Flash Update

Use *Dxxx-xyz.DFI.\$xe* for Windows-based BIOS update

→ Rename file to *.exe after download and run exe-file from MS Windows

Auto BIOS Update

With Auto BIOS Update it is possible to check a Fujitsu server automatically to see if there is a new BIOS version for the system. For the update, no operating system or external storage medium is required. This feature must be enabled in BIOS Setup first.

For details on the Auto BIOS Update function, see BIOS manual

BIOS Recovery

Copy the *.ROM file (included in the ZIP file) to the root directory of a FAT32 formatted bootable USB stick.

Power off mainboard, insert the USB stick, set the jumper in the front panel connector to the *BIOS Recovery* position (marked orange), then turn on the mainboard.

You will hear short beeps while the BIOS is recovered. Wait until you hear a series of "long-long-short-short" beeps. Then turn off the mainboard and move the jumper back to the standard position (marked orange and pink).

The BIOS Recovery process can take a few minutes.

1.3 Modify BIOS Setup Settings (Tool EditCMOS)

The file *EditCMOS_SetupItemID_Dxxx-yz.txt* provides an overview about the supported BIOS Setup items of this specific BIOS version for the tool EditCMOS (Modify BIOS Setup Settings). See EditCMOS tool for further details:

ftp://ftp.ts.fujitsu.com/pub/Mainboard-OEM-Sales/Services/Software&Tools/Common-Mainboard-Tools/EditCMOS_UEFI/

1.4 How to create a DOS bootable USB stick?

You can use the Fujitsu tool *FTS_Basic-BootStick.EXE* to easily create a Free-DOS bootable Stick: <ftp://ftp.ts.fujitsu.com/pub/Mainboard-OEM-Sales/Services/Software&Tools/Common-Mainboard-Tools/USB-FreeDOS-Bootstick/>

Rename file from *.*\$*xe to *.exe and run tool in Windows.

1.5 FTP BIOS Folder D3348-B

The released BIOS versions for D3348-B are available here:

ftp://ftp.ts.fujitsu.com/pub/Mainboard-OEM-Sales/Products/Mainboards/Industrial&ExtendedLifetime/D3348-B/BIOS_D3348-B/

1.6 Note: Customer Service Release BIOS

Besides the released BIOS versions there may be additional BIOS versions (Customer Service Release BIOS = CSR BIOS) that solve specific customer problems.

Please note: These versions are available via OEM FTP only and they are not pre-installed ex factory.

2 BIOS R1.3.0

First released mass production BIOS

Known Issues and Limitations:

- Intel Turbo Boost Max 3.0 not supported with BIOS R1.3.0. This will be solved with upcoming BIOS

3 BIOS R1.5.0

BIOS Changes vs. R1.3.0:

- Solved: MAC Address of LAN 2 not shown at BIOS Setup System Information.
- Solved: System hangs at POST with CATERR while booting with BIOS Recovery jumper set.
- Solved: POST error message during BIOS Flash Recovery (removed unsupported IDE recovery).
- Solved: BIOS Setup Event Log text "Virus detected" for "Virus Warning" was not defined.
- Solved: Boot Device in Boot Option Priorities appears twice.
- Feature: Intel Turbo Boost Max Technology 3.0 (For TBM3.0 default for CPU "HWPM Support" was changed from "Disabled" to "Native Mode").

Known Issues and Limitations:

- None

4 BIOS R1.6.0

BIOS Changes vs. R1.5.0:

- Solved: The system hangs up at CPU test done in Diagnostic Program (EVTE). System seems to hang, if multi-processing applications are running and simultaneous SMIs occur and the TeraDici remote access card is plugged. This may happen in late BIOS POST and DOS.
- Solved: After resume from S3 state, Memory ECC error (Single Bit Error and Multi Bit Error) is not logged in BIOS Event Log

Known Issues and Limitations:

- None

5 BIOS R1.10.0

BIOS Changes vs. R1.6.0:

- Updated to Management Engine Firmware version 9.1.41.3024.
 - Fix for INTEL-SA-00075 / CVE-2017-5689
 - **Please note:** BIOS is for new produced mainboards. If customers flash this BIOS version, the ME will not be updated during the flash process! Customers must use the LocalFW-Update tool to update the ME.
 - ftp://ftp.ts.fujitsu.com/pub/Mainboard-OEM-Sales/Services/Software&Tools/Miscellaneous/INTEL_SA-00075_ME-Update/
 - <http://support.ts.fujitsu.com/index.asp> > Peripheral Devices > Mainboards > Select a new Product > Product Search "D3348-B2" > Downloads > Driver > AMT

Known Issues and Limitations:

- None

6 BIOS R1.11.0

BIOS Changes vs. R1.10.0:

- Updated: System Monitoring characteristics
- Updated: CPU Microcode Patches
 - Haswell EP B0 = 80000014h
 - Haswell EP C0/C1/M1 = 0000003Ah
 - Broadwell EP B0 = 0B000022h
- Solved: UEFI IPv6 PXE boot not working properly.
- Solved: In BIOS setup / DOS the system does not switch off correctly with some CPU / PCIe card (USB3 PCIe card) combination.
- Solved: POST hang with some types of USB Cardreaders.
- Solved: No legacy boot from ODD's possible if SATA Mode=Raid.
- Feature: PCIe Slot 3 Slot Mode (Bifurcation) can be activated (for usage of PCIe riser cards) in BIOS setup [Advanced > PCI Subsystem Settings]
- Feature: Added several SetupItemIDs

Known Issues and Limitations:

- None


7 BIOS R1.14.0 [new]

BIOS Changes vs. R1.11.0:

- Updated: CPU Microcode Patches (INTEL-SA-00088, CVE2017-5715)
 - Haswell EP B0 = 80000014h
 - Haswell EP C0/C1/M1 = 0000003Ch
 - Broadwell EP B0 = 0B00002Ah
- Updated to Management Engine Firmware version 9.1.43.3004 (INTEL-SA-00086).
 - **Please note:** Intel ME will not be updated during BIOS flash due to missing Intel update support. Only possible in factory. Customers have to use the Local-Firmware-Update tool which is available on our FTP server or on the support page:
 - ftp://ftp.ts.fujitsu.com/pub/Mainboard-OEM-Sales/Services/Software&Tools/Miscellaneous/INTEL_SA-00086_ME-Update/
 - <http://support.ts.fujitsu.com/index.asp> > Peripheral Devices > Mainboards > Select a new Product > Product Search "D3348-B2" > Downloads > Driver > AMT
- Updated: System Monitoring Firmware
- Solved: Only 1.4GB RAM available after AMT PowerOn with selected Boot index.

Known Issues and Limitations:

- None



shaping tomorrow with you